



**ANALYSIS OF BEARING CAPACITY AND SETTLEMENT
OF BORE PILE FOUNDATION**

UNDERGRADUATE THESIS
Submitted as part of the requirements to obtain
Sarjana Teknik

By:

ORIZA SATIVA YONERI
022202000026

FACULTY OF ENGINEERING
CIVIL ENGINEERING STUDY PROGRAM

CIKARANG
OCTOBER, 2023

TURNITIN TEST RESULT

Analysis of Bearing Capacity and Settlement of Bore Pile Foundation

ORIGINALITY REPORT

18%

SIMILARITY INDEX

14%

INTERNET SOURCES

9%

PUBLICATIONS

7%

STUDENT PAPERS

PRIMARY SOURCES

1

dokumen.pub

Internet Source

1%

2

tuprints.ulb.tu-darmstadt.de

Internet Source

1%

3

theconstructor.org

Internet Source

1%

4

Rasyid Karami, Rina Yuliet, Elsa Eka Putri.
"Planning of the foundation a three-story
building constructed on potential liquefaction
area in Air Tawar Estuary of Padang City", E3S
Web of Conferences, 2021

Publication

1%

5

edoc.pub

Internet Source

1%

6

menglim498.files.wordpress.com

Internet Source

1%

GPT ZERO TEST RESULT

Your text is most likely human written

The nature of AI-generated content is changing constantly. As such, AI detection results should not be used to punish students. We recommend educators to use our behind-the-scenes [Writing Reports](#) as part of a holistic assessment of student work. See our [FAQ](#) for more information.

GPTZero Model Version: [2023-09-14](#)

CHAPTER I INTRODUCTION 1.1 Background The foundation is an important part of construction because it functions to withstand the load on it.

The foundation transmits the load into the ground which determines whether or not a building is stable.

Likewise the Refinery Development Master Plan (RDMP) project, which is a government policy to increase the country's energy security and encourage economic revitalization, in this case, the development of oil refinery facilities, which will reduce the country's dependence on foreign oil.

This project is implemented in Balikpapan, East Kalimantan by PT Kilang Pertamina Balikpapan which is a dependent organization of PT Pertamina (Persero).

This project is experiencing a fairly high level of difficulty because the new refinery is not built on vacant land but in the middle of the old refinery that is still operating.

Stats

Average Perplexity Score: 212.533

A document's perplexity is a measurement of the randomness of the text

Burstiness Score: 387.937

A document's burstiness is a measurement of the variation in perplexity

Your sentence with the highest perplexity, "Knowing the settlement of group piles 5.", has a perplexity of: 2477

ABSTRACT

This final project presents the bearing capacity and settlement that occurs on the bore pile foundation for a sulfuric acid tank with an operational weight of 796 kN, a diameter of 3 m, and a tank height of 6 m. The use of bore pile foundations is another alternative because there are existing buildings in the construction area. Bore pile foundation construction generally produces less vibration so it does not disturb existing buildings around the construction area. The foundation is crucial to the building's construction because it ensures the building's safety, stability, and structural integrity. Without a solid and powerful base, the structure can be severely damaged and even lead to a collapse.

Calculate bearing capacity and settlement with a bore pile foundation depth of 5,15 m, using variations in 40 cm and 30 cm diameter variations. Based on SPT data using the Reese & Wright method, the allowable carrying capacity of a single pile foundation for a diameter of 40 cm is 293,6 kN, and for a diameter of 30 cm is 201,9 kN. The bearing capacity of the pile group is also calculated, with the results for a bore pile foundation with a diameter of 40 cm, namely 1001,54 kN with a total of 4 piles, while for a pile diameter of 30 cm, it is 990,91 kN with a total of 6 piles, these values are greater than the axial load (P) which is 931,63 kN. The results of calculating the settlement of a single bore pile using the Vesic method is 3,24 cm, and the group settlement is 7,41 cm, while with a pile diameter of 30 cm, the settlement of a single bore pile is 2,41 cm and settlement in the pile group is 7,23 cm. The settlement that occurs in both variations of pile diameter is said to be safe or still at the tolerable limit because they are smaller than the allowable settlement, which is around 15 cm.

Keywords: Bore Pile, SPT, Bearing capacity, Settlement

ACKNOWLEDGEMENT

First of all, the author prays to God for the blessings and guidance you have given her. Your grace has been her strength and her source of hope in difficult times. The author is truly grateful for your love and mercy so that she can complete the thesis entitled "*Analysis of Bearing Capacity and Settlement of Bore Pile Foundation*" smoothly.

In completing this thesis, the author is aware that this thesis would not be completed without the guidance various parties' guidance, support, and assistance or wishes Dr-Ing. Erwin Sitompul, M.Sc as the Dean School of Engineering. Dr. Ir. B.M.A.S Anaconda Bangkara,M.T.,M.S.M as the Head of Civil Engineering Department. The same appreciation also goes to Prof. Ir. Binsar Hariandja, M.Eng., M.S., Ph.D. as her first thesis advisor for his guidance, encouragement, and valuable time in guiding her throughout the process of preparing this thesis, and to all Civil Engineering lecturers who have taught and guided the author.

The author always wants to express her deepest gratitude to all of her family, especially her father, and her mother, for their unwavering love, support, and encouragement which has been the strength of her life journey. The author obviously wants to thank herself, for the hard work, perseverance, and dedication that she has shown throughout this journey. It's not always easy, but she stayed committed and got through the challenges.

Last but not least, hopefully, the results of this research can provide benefits and can be a reference for students who will make a similar report. Of course, there are still shortcomings and errors in completing this final project. For this reason, constructive criticism and suggestions are highly expected so that they can be useful in the progress of the world of education.

Cikarang, October 2023

A handwritten signature in black ink, consisting of a large, stylized 'O' followed by a series of loops and a horizontal line at the end.

Oriza Sativa Yoneri

TABLE OF CONTENT

CHAPTER	TITLE	PAGE
	FINAL PROJECT REPORT APPROVAL PAGE	i
	PANEL OF EXAMINERS' APPROVAL	ii
	STATEMENT OF ORIGINALITY	iii
	SCIENTIFIC PUBLICATION APPROVAL	iv
	FOR ACADEMIC INTEREST	iv
	ADVISOR'S APPROVAL FOR PUBLICATION	v
	TURNITIN TEST RESULT	vi
	GPT ZERO TEST RESULT	vii
	ABSTRACT	viii
	ACKNOWLEDGEMENT	ix
	TABLE OF CONTENT	x
	LIST OF FIGURES	xii
	LIST OF TABLES	xiv
I	INTRODUCTION	1
1.1	Background	1
1.2	Scope of Work	2
1.3	Goal of The Research	2
1.4	Relevancy of The Work	3
1.5	Thesis Outline	3
II	SOIL INVESTIGATION AND BORE PILE FOUNDATION	4
2.1	General	4
2.2	Soil Test	4
2.2.1	Standard Penetration Test	5
2.3	Deep Foundation	8

CHAPTER	TITLE	PAGE
	2.3.1 Bore Pile Foundation	9
	2.3.2 Bore Pile Advantages and Disadvantages.....	10
	2.3.3 Bore Pile Construction Process.....	11
	2.4 Implementation Method.....	12
	2.5 Summary	12
III	BEARING CAPACITY AND SETTLEMENT	14
	3.1 General	14
	3.2 Bearing Capacity of Bore Pile Foundation	14
	3.2.1 Single Pile Bearing Capacity	15
	3.2.2 Pile Group Bearing Capacity	18
	3.3 Settlement of Bore Pile Foundation	19
	3.3.1 Settlement On Single Pile	20
	3.3.2 Settlement On Group Pile	21
	3.3.3 Allowable Settlement.....	21
	3.4 Summary	22
IV	EXAMPLE OF APPLICATION	23
	4.1 General	23
	4.2 Calculation of Bore Pile Foundation Capacity	24
	4.2.1 Calculation of Single Pile Bearing Capacity	25
	4.2.2 Arrangement of Piles	27
	4.2.3 Calculation of Pile Group Capacity	30
	4.3 Calculation of Single Pile Settlement	31
	4.4 Calculation of Pile Group Settlement	33
	4.5 Calculation of Allowable Settlement.....	34
	4.6 Summary.....	35
V	CLOSURE	36

CHAPTER	TITLE	PAGE
5.1	Summaries.....	36
5.2	Conclusions.....	36
5.3	Proposal for the Continuing Research	37
REFERENCES		38
APPENDICES		40
A: SPT Data		40
B: Bearing Capacity Calculation		43

LIST OF FIGURES

FIGURE	TITLE	PAGE
2.2.1:	The SPT Sampler	6
2.2.2:	Standard Penetration Test Tools.....	7
2.3.1:	Types of Bore Pile	10
2.3.2:	Stages of Bore Pile Foundation	12
2.4.1:	Research Flowchart.....	13
3.2.1:	The Pile In Terms of How It Supports Its Load (Hardiyatmo,2008).....	15
3.2.2:	Comparison of Sressed Zones Beneath Single Pile and Pile Group.....	18
4.2.2:	Arrangement of Piles Ø30 cm	29

LIST OF TABLES

TABLE	TITLE	PAGE
2.2.1:	Correction Table for Field Procedure of SPT N-Value	8
3.2.1:	Relationship of N to relative density (Dr)	15
3.3.1:	The value of the empirical coefficient (Cp).....	21
4.1.1:	Nspt Correction.....	23
4.1.1:	Nspt Correction (continuation)	24
4.2.1:	Calculation of Bore Pile Bearing Capacity (Ø40 cm)	26
4.2.2:	Calculation of Bore Pile Bearing Capacity (Ø30 cm)	27
4.2.3:	Recapitulation of Allowable Capacity	27
4.2.4:	Recapitulation of Pile Group Capacity	31
4.3.1:	Settlement on each layer, with a pile diameter of 40 cm.....	32
4.3.2:	Settlement on each layer, with a pile diameter of 30 cm.....	32
4.3.3:	Recapitulation of Single Pile Settlement	33
4.4.1:	Recapitulation of Pile Group Settlement	34
4.5.1:	Recapitulation of Bore Pile Settlement.....	34